



Република Србија  
Аутономна Покрајина Војводина  
Град Суботица  
Број: П-401-862/2017-1  
Дана: 04.04.2018.  
24000 Суботица  
Трг слободе 1.

### CONTRACTING AUTHORITY'S CLARIFICATIONS No. 3

Contract title: **Construction of the Tourism and Cultural Centre in Palic for project: "Colourful Cooperation"**

Publication Ref: **HUSRB/1601/31/0005-B3-7.1.1**

No.	Question	Answer
1.	<p>Part: 3. WATER SUPPLY, POSITION 3.17.: „Procurement, transport and installation of a combined water meter <u>DN65</u> for measuring the spent water, for anti-fire water. Calculation per a piece.“ DN 65 does not exist, only exist DN 50, DN 80 and DN 100. Which of the above, which exist, we offer? Then, position 3.17 and position 3.18.: JKP water supply and sewage system Subotica can not place two water meters as you ask position 3.17 and 3.18 one for fire water, the other for sanitary water, <b>but only one.</b></p>	Please refer to Corrigendum No. 3.
2.	<p>Part: 4. SEWERAGE, POSITION 4.10: „Making of connection to the existing sewerage system. Connection should be executed in accordance with the requirements of competent utility service, this design and conditions on site. Calculation per a flat rate“. - From JKP water supply and sewage system Subotica give the answer that there <b>is no existing sewage network</b> on that part, and therefore they can make a connection, to remind, they are the only authorized to do this.</p>	Please refer to Corrigendum No. 3.
3.	<p>Please clarify the following questions for the object: Construction of the Tourism and Cultural Centre in Palic for project: "Colourful Cooperation", under the Publication ref. No. HUSRB/1601/31/005-B3-7.1.1. 1. In the BoQ, Architecture works - 3. Masonry</p>	Unit for Item 3. Masonry works; position No.5 (Architecture works) is m <sup>2</sup> .

	<p>works, position No. 5 with the description: "Erect partition walls w=12cm, with cellular concrete blocks. Blocks should have a flat surface and sharp edges (e.g., Ytong or similar). Walls should be made in a thin-layer of mortar that is recommended by the manufacturers of blocks. Mortar should be deposited on the block with special knives max. 3mm.</p> <p>Height of walls in the attic approx. 250cm</p> <p>The price should include necessary scaffolding, all the materials, labour, and transport.</p> <p>Calculated per a m3.</p> <p>Q: In the unit field stands sq.m. Please clarify, for which unit should the price be given.</p>	
4.	<p>Is it enough we deliver to the our offer only a list of offered material with the country of origin, and attest to the same material for getting the job - after installation of materials?</p>	<p>As stated in Article 12.1 of Instruction to tenderers of VOLUME 1. Among others all tenders must comprise the following information and duly completed documents:</p> <ul style="list-style-type: none"> <li>• a list of materials and any supplies intended for use in the works, stating their origin;</li> </ul>
5.	<p>4.3.2 — Bill of Quantities, ELECTRIC INSTALLATIONS</p> <p>1. SUPPLY</p> <p>Works on the installation of measuring cabinet OMM. Manufacture according to ED requirements, including the manufacture of NN terminal and connection to MBTS, laying and connection of supply cable from MBTS to OMM, issuing of approval and obtaining of required documents</p> <p>Material will all necessary works.</p> <p>Note: Is the offer for the position above expected, since the works are carried out by the power distribution company?</p>	<p>Yes, the offer for the position above expected. If some works need to be completed by related utility company during construction works, supervisor will regulate those specific works.</p>
6.	<p>4.3.2 — Bill of Quantities, ELECTRIC INSTALLATIONS</p> <p>4. LIGHTS AND SOCKETS</p> <p>7. Delivery and mounting of lights with starters, suitable light bulbs and accessories for mounting, all together with connecting. The specific type and manufacturer for lights will be defined by the interior designer:</p> <ul style="list-style-type: none"> <li>- fluo 2x36W IP65</li> <li>- fluo 2x49W</li> <li>- mountable fluo COMPACT 2x26W</li> <li>- mountable fluo COMPACT 50W on the wall</li> <li>- mountable fluo COMPACT 26W on the wall, outside</li> <li>- mountable 20W/220V</li> <li>- fc lamp 2x18W 230V</li> <li>- reflector MH 70 W, IP65</li> <li>- Anti-panic 1x8W with marking of evacuation direction, 1h autonomy, surface mounted,</li> <li>- decorative interior lamp 50W</li> </ul>	<p>Tenderer needs to provide offer for lighting in line with specification including technical details regarding offered lighting. Lamp type and manufacturer is open to tenderer.</p>

	<ul style="list-style-type: none"> <li>- decorative interior lamp 26W</li> <li>- decorative outside lamp 100W</li> <li>- decorative hanging lamp 50W</li> <li>- fluo lamp 18W IP55</li> <li>- Ceiling lamp 100W</li> </ul> <p>Note: Has the interior designer completed the project? How to offer lighting when we do not have a lamp type, manufacturer or characteristics?</p>	
7.	<p>4.3.2 — Bill of Quantities, ELECTRIC INSTALLATIONS</p> <p>4. LIGHTS AND SOCKETS</p> <p>10. Delivery and laying non-inflammable cable console above the dropped ceiling</p> <ul style="list-style-type: none"> <li>- PNK 100</li> <li>- PNK 400</li> </ul> <p>Note: Cable console must be non-inflammable above the dropped ceiling?</p>	<p>Yes, cable console must be non-inflammable above the dropped ceiling.</p>